



**TECHNICAL DATA SHEET**



**Kiosk Enclosure**

**\*image of a similar transformer unit.**



## 1. Technical Data

Item 1 – Dry Type Transformer		HV Winding 1	LV Winding 1
Rated power	kVA	500	500
Rated voltage	kV	0.415/11/22/33	0-1 kV
Frequency	Hz	50	
Off circuit tapping links	%	±2.5%, +5%	Nil
Connection		Star/Delta	Star/Delta
Vector group		Dyn11	
Insulation level (Maximum BIL/AC)	kV	(145-20)/(3-70)	(145-20)/(3-70)
Winding material		Aluminium/Copper	Aluminium/Copper
Type of winding		Oil Type	Oil Type
Standard		AS 60076-11, AS 2374	
Installation		Indoor/Outdoor	
Degree of protection		IP00-IP56	
Type of cooling		ONAN	
Installation altitude		< 1000 a.m.s.l	
Climatic/environmental and fire behaviour class		E2-C2-F_(0/1)	
<b>Indicative values</b>		<b>Reference Temperature: 75°C</b>	
Standard tolerances per AS 60076 are applicable to the following values			
No-load loss	W	510	
Load loss	W	3960	
Impedance	%	4-6%	
Efficiency @ 75degC	50% /75%/100% Load	98.60/98.85/99.04 (MEPS COMPLIANT)	
<b>Insulation Class</b>			
Max.ambient temperature	°C	45	
		HV winding	LV winding
Insulation temperature class		A	
Temperature rise	°C	100	
<b>Overall dimensions and weights (Preliminary)</b>			
Width x Depth x Height (IP00)	mm	1700 x 1160 x 1300	
Mass (IP00)	Kg	1550	
NOTE: losses dimensions and weights are indicative, to be confirmed following receipt of purchase order and completion of engineering stage.			
<b>Accessories</b>			
<b>STANDARD (FOR EA TRANSFORMER)</b>		<b>UNITS</b>	
HV terminals		3	HV bushing
LV terminals		4	LV bushing
Rating plate		1	Stainless Steel
Radiator		Yes	
Oil Temperature Thermometer		Yes	



# TorTech

30 Years as Australia's transformer specialist



Pressure Relief Valve	Yes	
Oil Level Indicator	Yes	
Dain & Filling Valve, Earth Terminal	Yes	
Lifting Lugs	Yes	
<b>Routine tests (Included)</b>		
<b>Winding resistance</b>	Yes	
Ratio and phase relationship	Yes	
Impedance voltage, short circuit impedance and load loss	Yes	
No load loss	Yes	
Induced over voltage withstand	Yes	
Separate source voltage withstand	Yes	
Insulation resistance	Yes	
<b>Type tests (Optional – additional cost)</b>		
Temperature rise test	Yes	
Impulse test	Yes	
Noise pressure level test	Yes	

Drawings issued 1 week after the order.

Project timeline issued 2 weeks after order.

Inspection and Test Plan, Operation and Maintenance manuals submitted 4 weeks prior to delivery.